

Fractured Rock Aquifer Sustainability






Water Cycle and Groundwater






Definition of Fractured Rock Aquifer



Fluvial Aquifer


Water exists in spaces between grains (primary porosity). Carmel Valley Alluvial Aquifer



Fractured Rock Aquifer

Water exists in fractures in non water bearing rocks (secondary porosity).





Quality of Fractured Rock Aquifer

"Quality" in this context is defined as ability of aquifer to store and transmit water.

Poor Quality (low yield) Fractured Rock Aquifer **High Quality (high yield) Fractured Rock Aquifer**


Little to no Non-connected small Connected small Connected small and fractures fractures fractures large fractures

Sustainability of an Aquifer

- Production of water from any aquifer is sustainable when recharge is equal to or greater than production (safe yield).
- Changes in groundwater storage are observed through changes in water levels. Falling water levels over time indicate reduction of stored water and non-sustainable production.



• Long-term water level monitoring has not been completed within the pilot study area.





Motivation for Study

- Due to limitations on new water connections from the Cal-Am system, many land owners/developers have begun to drill groundwater wells as a source of supply to new or planned developments.
- Permits for wells are issued based upon performance of the well following drilling.
- A Water Distribution System Permit (WDS) does not guarantee a water for the life of the development.
- Can we learn anything from the data we already have in our files?















Fractured Rock Study Schedule to Date




Sources of well records

- Department of Water Resources
- •MPWMD Well/Parcel files
- Monterey County **Environmental Health** Well Permitting
- Monterey County Water **Resources District**




Fractured Rock Wells Within MPWMD Boundaries



Fractured Rock Well Status

Sources of Well Status

- •MPWMD well reporting
- Monterey County
 Environmental Health
 Destruction Records
- Monterey County WaterResources Agency






Moving from Lithology to a Hydrogeologic Framework Model


Enter Lithology Data into Database


Group Lithology into Hydrogeologic Units

Assign Wells to Corresponding Hydrogeologic Unit









EXPLANATION


Tm = Monterey Formation (porcelanite) - (Mocene) - Light brown to white, hard, britile, platy.

Tis = Chamisal Sandstone (Microene) - Marine deposition; buff to light-gray, poorly to well sorted arkosic sandstone, locally triable, locally conglomeratic.

Kgd = Granodiorite to Quartz Monzonite Basement Complex (Cretaceous)

NOTES:

This geologic cross section is a graphical representation only. Data used to create this cross section was obtained from Geologic Map (Figure 3) and Department of Water Resources Well Completion Report(s) - Appendix A. Faults (if applicable): Actual fault offset, and dip is uncertain. Fault motion is correct.





CONCEPTUAL GEOLOGIC CROSS SECTION A-A'

APN: 103-102-016 & 017 Monterey County, California FIGURE 4

Orawn By. IAB, 460 (69 Felix tercoFigures/A-A[†].cv

Representative Hydrogeologic Unit Outcrops Exposed in Road Cuts

Unconsolidated Sediments

Monterey Shale

Granitic Basement











Assigning Wells to the Hydrologic Framework Model

Well screen intervals reported on DWR driller logs were used to assign the appropriate section of the Hydrogeologic Framework Model where each well primarily extracts water.




Fractured Rock Screened Lithology











Granitic Section of the Hydrogeologic Framework Model









Well Performance – Aquifer Quality

Pumping tests are performed upon well completion to calculate the ability of well to produce water.


- MPWMD water distribution system permits require 72 hour pumping tests during permitting process
 - Good quality data
 - Accurate aquifer parameters
 - Consistent methodology
 - Poor geographic coverage
- DWR pumping test
 - Data often incomplete
 - Can not be used to calculate aquifer parameters
 - Inconsistent methods
 - Good geographical coverage






These calculations are completed on data collected following well construction and are therefore a measure of how the well performed when it was new and not the sustainability of the well.

MPWMD Well Yield Calculation for Water Distribution System Permit



- **Available Drawdown** = 1/3 (depth to bottom of perforations Static Water Level)
- Specific Capacity¹ = GPM / Drawdown
- Calculated well yield = Specific
 Capacity¹ * Available Drawdown
- Poor Geographical Coverage

DWR Drawdown Ratio



- Driller reports often do not report drawdown associated with pumping tests.
- In an attempt to normalize flow rate data reported on Drillers logs with depth, we created a "Drawdown Ratio."
- Drawdown Ratio = GPM / (Static Water Level – Depth to Bottom of Screens)
- Good Geographical Coverage


Distribution of Wells with MPWMD Well Yield Calculations

Prior to 2000, wells located on the same parcel as proposed water use did not require a Water Distribution System.

Replacement wells and Water Distribution Systems that qualify of exemptions do not require this test.



Fractured Rock Well Source Tests



Distribution of DWR Well Logs Containing Pumping Data

Much greater distribution of data, however not all pump tests were completed using the same methods.


Permanent vs. Temporary Pump

Airlift Method

Do these less consistent methods lend reliable results?



Fractured Rock Wells Within MPWMD Boundaries




Comparison of Methods

When comparing DWR Drawdown calculations with Accepted well yield Calculations, they were within 20% of one another.

Wells producing water from the Monterey Shale had a slightly higher correlation than wells producing from the Granite.


Parameter Analysis





Distribution of DWR Drawdown Ratio by Hydrogeologic Framework Unit

On the average, wells extracting water from the Monterey Shale component of the Hydrogeologic Framework Model Scored 0.064 GPM/ft better than wells extracting water from the Granitic component.




DWR Drawdown Ratio (gpm/ft)

What does this mean?



Monterey Shale vs. Granitic Basement

For two identically constructed wells one in the Monterey Shale and one in the Granite and both with 200 feet of available drawdown, their production volumes




Estimated DWR Drawdown Ratio

Geostatistical analysis of wells with DWR Drawdown Ratio allow the District to 'Predict' the DWR Drawdown Ratio within some of the fractured rock regions of the District.

District staff use this map to help identify regions to seek monitor wells.







Quail Meadows: Predicted DWR Drawdown Ratio

The terrace above the valley floor on which Quail Meadows is located was formed by a large translational landslide that occurred 30,000 Years ago.

Wells in this region are screened in the Monterey Shale and exhibit high DWR Drawdown Ratios.









Laureles Grade Transition: Predicted DWR Drawdown Ratio

Laureles Grade Transition Zone is formed as the **Laureles and Turlacitos** Fault Zones juxtapose the **Granitic Basement against** the Monterey Shale and overlying River Terrace near Carmel Valley Village.

Wells screened in the Granitic Basement do not exhibit as high a DWR Drawdown Ratio as wells screened in the Monterey Shale or the River Terrace.









Reported Annual Production

Reported production includes all source areas designated as fractured rock source areas within MPWMD boundaries.





Production Breakdown by Water Year







Groundwater Level Monitoring

MPWMD staff have purchased and deployed six continuous water level loggers in fractured rock source areas beginning in January 2011. Monitoring locations have moved as staff adaptively monitors fractured rock wells.

Fractured Rock Monitoring Well Adaptive Monitoring Decision Process




Hydrographs from Selected Monitor Wells





These are short term water level records that give us focused information on response of aquifer to pumping and recharge. Are there any long term trends available in the District's well files?

Depth of well by Drill Date





On average, depths wells completed have increased since 1960. This trend could represent declining water levels, but could also be influenced by advancements in drill technology making deeper wells more affordable.

Conclusions

- Findings of Pilot Study were validated for District Scale Study.
 - Monterey Shale exhibits higher DWR Drawdown values than the Granitic Basement.
- More water level data is necessary to understand sustainability of fractured rock wells.
- Additional ongoing data collection is needed to help define and focus on areas of special concern.
- WDS process will provide more data regarding replacement of inadequate wells moving

MONTERET OR WHENEVER


Management District

Recommendations

- Continue to add to database;
 - DWR drawdown
 - WDS pump test data
 - Lithology/Hydrogeologic Framework
 - Production
- Continue to use predicted DWR Drawdown to refine the understanding of geologic control of well performance.
- Continue to collect water level data and adaptively monitor fractured rock wells;
 - Help with understanding of sphere of influence/recharge zones for wells for differing materials.
- Complete a larger scale broadcast water level monitoring effort.
 - Identify on a regional scale if water levels have fallen since wells were drilled.
- Amend WDS rules to include water level data collection as a component of the process for fractured wells.
- Commence effort to understand recharge to fractured rock aquifers.




Example of WDS Process and Replacement Well Data Generation



Data from Monitor well


- Drilled as Production well in 6/2005
- •72 hour pump test completed as requirement for WDS permit.
- •Well produced 6.2 GPM over the test and pumping water level was 19 feet below static.
- •An observation well 550 feet from the pumping well was monitored and considered to be hydrogeologically disconnected from the pumping well.
- •In June 2005 static water level was 344 feet BGS compared to June 2010 when static water level was measured to be 459 feet BGS.
- •A total of 4.5 acre-feet was produced from the well between 2005 and 2010.
- •A replacement well has been drilled 500 feet from the monitoring well and is not hydrogeologically connected to the monitor well.

Understanding Recharge to Fractured Rock Systems by Indirect Methods





Analysis of Baseflow Hydrographs





Threshold for Water Years Providing Baseflow to Pine Creek

