



BID ADDENDA 3 – March 7, 2022

SLEEPY HOLLOW STEELHEAD REARING FACILITY QUARANTINE TANKS REPLACEMENT

Item 8 – Hand excavation

- This Addendum updates language in the plans and specifications for the project that require hand excavation to avoid damage to existing utilities. After removal of the quarantine deck, the District Engineer will carry out an inspection with the Contractor to determine the feasibility of using mechanical equipment for excavation work.
- Methods to determine whether machine or hand excavation should be used include potholing by hand to determine end member locations of utilities and/or use of underground utility locator equipment.
- If the District Engineer and Contractor agree that mechanical equipment may be used for excavation, the Contractor shall be responsible for documenting the existing locations of utilities (such as with labeled photos or on the plan set) and reconstructing all utilities removed during excavation.